

Financial Year	Budget	Structure Number	Structure Name	Estimate	Work Req'd	Road No	Road Name	Obstruction Name
2017-2018	835,000	98	Gas Works	225,000	repairs and painting. Maintain as footbridge.	Uncl	Gas Works Road	River Calder
			Walls	110,000	Wall collapses	Various		
			Pexwood Road Walls	250,000	Soil Nailing to burr wall	Uncl	Pexwood Road	Land
			Shaw Wood Road Canal Bridge	150,000	Widening of Canal Bridge			
			Insp & Assessment	100,000				
2018-2019	805,000	175	Brighouse	350,000	Paint Truss parapet	A641	Huddersfield road	River Calder
			Walls	130,000	Wall Collapses	Various		
		1110	Sandyfoot Clough	70,000	Artch Repairs		Branch Road	
		80	Cob Clough	150,000	Rebuild leaning spandrel & parapet	B6113	Elland Road	Cob Clough
			Insp & Assessment	105,000				
2019-2020	735,000	195	Brighouse Canal	445,000	Reconstruct footway widenings each side.	A641	Huddersfield Road	Calder & Hebble Navigation
		134	Brow	75,000	Paint plus steelwork repairs	B6113	Rochdale Road	Black Brook
		2	Lineholme	50,000	Concrete repairs	A644	Burnley Road	River Calder
		3	Scaitcliffe	30,000	Concrete repairs	A646	Burnley Road	River Calder
		3	Scaitcliffe Extension	30,000	Concrete repairs			
			Insp & Assessment	105,000				
2020-2021	720,000	4108	Gooder Lane	250,000	Fails assessment strengthening req'd		Gooder Lane	Railway
		87	Stirk	260,000	Painting and strengthening New deck.	Uncl	Bridge Street	River Ryburn
		164	Ainley Top	105,000	New Parapets	A629	Old Linley road	Calderdale Way
			Insp & Assessment	105,000				
2021-2022	855,000	4016	Hall Royd Road	750,000	Fails assessment strengthening req'd Railway Bridge		Hall Royd Road	Railway
			Insp & Assessment	105,000				
2022-2023	795,000	192	Golden Lion Canal	285,000	Reconstruct widenings	A6033	Rochdale Road	Rochdale Canal
		217	Dulesgate	410,000	Poor lcondition Cast In Situ Deck Reconstruct ?	Uncl	Bacup Road	Dulsegate Water
		6	Walsden New	100,000	Deck Reconstuction	A6033	Rochdale Road	Walsden Water